## COURTENAY, BC



# **Client:**

BARTLE AND GIBSON CO. LTD.

# **Project:**

COMMERCIAL DEVELOPMENT 4625 MADRONA PLACE

# **Engineering Services Provided by:**



www.wedler.com

THE WEDLER GROUP

- Abbotsford 1.604.746.0300
- Chilliwack 1.604.792.0651
- Courtenay 1.250.334.3263
- Surrey 1.604.588.1919

# **Drawing Index:**


Drawing No.	Issue	Title of Drawing
V22-0522/A-00	С	COVER AND SITE LOCATION PLAN
V22-0522/A-01	С	KEY PLAN
V22-0522/A-02	С	SITE SERVICING
V22-0522/A-03	С	STORMWATER MANAGEMENT AND GRADING PLAN
V22-0522/A-04	С	EROSION AND SEDIMENT CONTROL PLAN
V22-0522/A-05	С	GENERAL NOTES, STORM CALCULATIONS AND MISCELLANEOUS DETAILS
V22-0522/A-06	С	EMERGENCY 100-YEAR OVERFLOW ROUTE


REVISION C


# Project No: V22-0552/A Date: SEPTEMBER 2022


















### **EROSION & SEDIMENT MANAGEMENT**

- ALL WORK IS TO BE UNDERTAKEN AND COMPLETED BY THE CONTRACTOR IN SUCH MANNER AS TO PREVENT THE RELEASE OF SILT, SEDIMENT OR SEDIMENT LADEN WATER, CONCRETE OR CONCRETE LEACHATE, OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY STORM SEWER, LAWN DRAIN, SOAK-AWAY, DRY WELL OR WATERCOURSE. (SEDIMENT LADEN WATER MAY BE DISCHARGED TO STORM SYSTEMS THAT ARE USED TO CONVEY FLOWS TO A SEDIMENT MANAGEMENT FACILITY).
- 2. INSTALL TEMPORARY PIPES, SWALES, CULVERTS, ETC. AS REQUIRED TO DIRECT SEDIMENT LADEN FLOWS TO SEDIMENT MANAGEMENT FACILITIES. REMOVE TEMPORARY WORKS WHEN NO LONGER NEEDED. BACKFILL WITH MATERIALS AND LEVELS OF COMPACTION AS RECOMMENDED BY THE GEOTECHNICAL ENGINEER.
- 3. TO PREVENT EROSION:
- a. PREVENT CONCENTRATED OVERLAND FLOWS FROM OCCURRING COVER STOCKPILES, EXPOSED EARTH AND DISTURBED AREAS WITH STRAW OR BY OTHER COVERINGS.
- LIMIT CLEARING AS MUCH AS POSSIBLE TO AREAS TO BE IMMEDIATELY WORKED.
- 4. PREVENT WIND BLOWN EROSION BY WATERING, COVERING EXPOSED EARTH OR BY OTHER APPROVED MEASURES. 5. CONTRACTOR TO INSTALL EROSION & SEDIMENT MANAGEMENT WORKS BEFORE ANY OTHER WORK, INCLUDING CLEARING AND EARTHWORKS,
- 6. ALL EROSION & SEDIMENT MANAGEMENT WORKS TO BE MAINTAINED BY THE CONTRACTOR AT ALL TIMES TO ASSURE PROPER OPERATION. REPLACEMENT OF FENCES AND/OR BERMS, THE FLUSHING OF SEWERS AND THE CLEANING OF SUMPS MAY BE REQUIRED DURING THE COURSE OF CONSTRUCTION.
- REMOVE AND DISPOSE OF ACCUMULATED SEDIMENT FROM SEDIMENT MANAGEMENT FACILITIES ON OR BEFORE SEDIMENT REACHING ONE THIRD
- THE HEIGHT OF THE FACILITY. MONITOR EROSION AND SEDIMENT MANAGEMENT WORKS AT LEAST ONCE PER WEEK AND AFTER HEAVY RAIN OR SNOW MELT EVENTS.
- BEFORE CONSTRUCTION ACTIVITIES, CONTRACTOR TO CLEAN EXISTING SUMPS AND FIT EXISTING CATCH BASINS & LAWN DRAINS WITH A FILTREXX INLET SOXX OR APPROVED EQUIVALENT TO PREVENT SEDIMENT FROM ENTERING ANY STORM SYSTEMS. DO NOT USE FILTER FABRIC.
- 10. ALL EROSION & SEDIMENT MANAGEMENT WORKS ARE TO REMAIN IN PLACE UNTIL BUILDING ACTIVITIES ARE 90% COMPLETE AND UNTIL VEGETATION HAS DEVELOPED ON EXPOSED AND DISTURBED AREAS WHICH CONTRIBUTE FLOWS TO THE EROSION & SEDIMENT MANAGEMENT
- 11. DEVELOPMENT PERMIT HOLDER (THROUGH THE CIVIL CONTRACTOR) SHALL BE RESPONSIBLE TO PROVIDE EROSION AND SEDIMENT CONTROL
- AS NECESSARY TO PREVENT THE RELEASE OF SEDIMENT OR SEDIMENT LADEN WATERS FROM ENTERING THE CITY DRAINAGE SYSTEM. 12. THE DEVELOPER SHALL DESIGNATE AN EROSION AND SEDIMENT CONTROL MONITOR TO BE RESPONSIBLE FOR THE INSPECTION AND DIRECTION
- OF REQUIRED MAINTENANCE OF THE IMPLEMENTED EROSION AND SEDIMENT CONTROL MEASURES. 13. THE EROSION AND SEDIMENT CONTROL MEASURES SHOWN ON THIS PLAN ARE THE MINIMUM LEVEL OF CONTROLS REQUIRED FOR THIS
- PROJECT.
- 14. CONTRACTOR AND BUILDER MUST SWEEP AND CLEAN PAVED OFFSITE ACCESS ROADS OF AT THE END OF EACH WORK DAY. NO SOIL OR SEDIMENTS SHALL BE DEPOSITED OR STORED OUTSIDE THE PROPERTY BOUNDARIES. WASHING OF ROADWAYS IS NOT PERMITTED.
- 15. DEVELOPER IS TO ENSURE THAT THE BUILDER IS MADE AWARE OF THE EROSION AND SEDIMENT CONTROL MEASURES AND OF THEIR RESPONSIBILITY TO MAINTAIN DURING CONSTRUCTION AS DIRECTED BY THE DEVELOPER'S EROSION AND CONTROL MONITOR.

### PROPOSED SEQUENCE OF CONSTRUCTION TO FACILITATE SILT CONTROL

- 1. INSTALL 'BMP SUPPLIES' SILT SAC OR APPROVED ALTERNATE ON ALL EXISTING STORMWATER INLETS.
- 2. INSTALL GRAVEL WASHDOWN PAD.
- 3. INSTALL PROPOSED STORM WORKS AS SHOWN.
- 4. INSTALL 'BMP SUPPLIES' SILT SAC OR APPROVED ALTERNATE ON ALL NEW CB MANHOLES.
- 5. CONSTRUCT CUTOFF DITCHES.
- 6. CONSTRUCT SEDIMENTATION POND
- 7. INSTALL ABOVE GROUND SEDIMENTATION TANKS.
- 8. EARTHWORK OPERATIONS SHALL BE CONDUCTED IN SUCH A WAY THAT EXPOSED UNPROTECTED AREAS ARE MINIMIZED. TEMPORARY STOCKPILES OF MATERIAL AND ANY EXPOSED SLOPES SHALL BE COVERED WITH STRAW, WOOD CHIPS OR OTHER COVERINGS TO PREVENT EROSION. ALL EXPOSED AREAS WHICH WILL BE DORMANT FOR A PERIOD OF LONGER THAN 30 DAYS SHALL BE SEEDED AND STABILIZED WITH NATIVE VEGETATIVE SPECIES.




OR STEEL POST


SILT FENCE DETAIL

N.T.S.


NOTE:
THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. GRAVEL WASH-DOWN PAD DETAIL <u>N.T.S.</u>




CROSS-SECTION <u>N.T.S.</u>




'L' = THE DISTANCE SUCH THAT POINTS 'A' AND 'B' ARE OF EQUAL ELEVATION.




PERIMETER CUTOFF DITCH c/w ROCK CHECK DAMS <u>N.T.S.</u>













THE WEDLER GROUP
■ Abbotsford 1.604.746.0300
■ Chilliwack 1.604.792.0651

1.604.588.1919


Surrey

Courtenay 1.250.334.3263

BARTLE AND GIBSON CO. LTD. COMMERCIAL DEVELOPMENT - 4625 MADRONA PLACE COURTENAY, BC LOCAL GOVERNMENT FILE EROSION AND SEDIMENT CONTROL PLAN REVISION

www.wedler.com

# UTILITY TRENCH DETAIL PER MMCD DWG G4



### **GENERAL NOTES**

- 1. ALL WORKS, MATERIALS AND TESTING SHALL BE IN ACCORDANCE WITH THE CURRENT CITY OF COURTENAY SUBDIVISION AND DEVELOPMENT SERVICING BYLAW 2919 AND THE CURRENT ISSUE OF THE MASTER MUNICIPAL CONSTRUCTION DOCUMENTS. ALL TESTING SHALL BE PERFORMED BY A CERTIFIED TESTING COMPANY AT EXPENSE TO THE CONTRACTOR.
- 2. ALL DIMENSIONS AND ELEVATIONS ARE METRIC.
- 3. INFORMATION ON THE DRAWINGS REGARDING EXISTING UTILITIES WAS COMPILED FROM MUNICIPAL RECORD DRAWINGS, CONSTRUCTION DRAWINGS AND FIELD SURVEYS. THIS INFORMATION IS NOT NECESSARILY ACCURATE OR COMPLETE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DATA BY EXPOSURE PRIOR TO ANY CONSTRUCTION AND TO IMMEDIATELY REPORT ANY DISCREPANCIES TO THE ENGINEER IF REMEDIAL ACTION IS REQUIRED. ANY CLAIMS RESULTING FROM THE CONTRACTOR'S FAILURE TO DO SO SHALL BE AT THE CONTRACTOR'S EXPENSE.
- 4. PRIOR TO ANY WORKS, THE CONTRACTOR SHALL ASCERTAIN FOR HIMSELF OF THE EXACT LOCATION OF BOUNDARIES OF LEGAL PROPERTIES, RIGHT—OF—WAYS OR EASEMENTS. ANY COST RESULTING FROM SPECIAL CONSTRUCTION METHODS, EQUIPMENT OR MATERIALS REQUIRED TO PERFORM ANY WORKS FORMING PART OF THIS CONTRACT WITHOUT ENCROACHING ON OR CAUSING DAMAGE TO OTHER PROPERTY, SHALL BE INCLUDED IN THE CONTRACT PRICE AND NO ADDITIONAL PAYMENT WILL BE MADE FOR SUCH WORKS.
- 5. THE CONTRACTOR SHALL PHOTOGRAPH, PRIOR TO CONSTRUCTION, ANY EXISTING FEATURES TO BE DISTURBED. THE CONTRACTOR SHALL RESTORE ALL DISTURBED PAVEMENT, CURBS, SIDEWALKS, LANDSCAPING, FENCES OR ANY OTHER FEATURES, INCLUDING MUNICIPAL AND THIRD PARTY UTILITIES INFRASTRUCTURE, AFFECTED BY THE CONSTRUCTION WORKS TO ORIGINAL CONDITIONS OR BETTER, AND TO THE SATISFACTION OF THE CONSULTANT AND THE CITY OF COURTENAY.
- 6. THE CONTRACTOR MUST CONTACT THE CITY OF COURTENAY & WEDLER ENGINEERING PRIOR TO CONSTRUCTION TO SCHEDULE A PRE—CONSTRUCTION MEETING DURING WHICH CONSTRUCTION METHODS, TIMING AND INSPECTIONS WILL BE DISCUSSED.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION LAYOUT.
- 8. CHANGES TO THE DESIGN MUST BE REVIEWED AND APPROVED IN WRITING BY WEDLER ENGINEERING AND THE CITY OF COURTENAY. FAILURE TO DO SO IN ADVANCE OF CHANGES MAY RESULT IN REJECTION OF WORK.
- 9. ALL MATERIALS TO BE SUPPLIED BY THE CONTRACTOR. SUBSTITUTION OF ANY MATERIAL SPECIFIED WITH A MATERIAL EQUAL OR BETTER IN QUALITY OR PERFORMANCE WILL BE PERMITTED ONLY WITH THE REVIEW AND EXPRESS WRITTEN APPROVAL OF BOTH THE CITY OF COURTENAY AND WEDLER ENGINEERING.
- 10. THE CONTRACTOR SHALL NOTIFY WEDLER ENGINEERING A MINIMUM OF 48 HOURS PRIOR TO REQUIRED INSPECTIONS INCLUDING, BUT NOT LIMITED TO THE FOLLOWING:
  - A. MOBILIZATION
  - B. DURING PIPE LAYINGC. DURING PREPARATION OF PAVEMENT STRUCTURE
  - D. DURING CONSTRUCTION OF DETENTION FACILITIES
    E. TESTING OF ALL UTILITIES
  - F. AFTER COMPLETION OF ALL WORK
- 11. TRENCHES ACROSS EXISTING PAVEMENT, CURBS, SIDEWALK AND BOULEVARDS SHALL BE REINSTATED IN COMPLIANCE WITH THE MUNICIPAL SPECIFICATIONS AND STANDARD DRAWINGS AND RECOMMENDATIONS OF THE GEOTECHNICAL ENGINEER.
- 12. ALL EARTHWORKS, MATERIALS, SUBGRADE AND PAVEMENT STRUCTURE TO BE APPROVED BY A GEOTECHNICAL ENGINEER, AND TO COMPLY WITH THE GEOTECHNICAL SITE ASSESSMENT PREPARED BY SIMPSON GEOTECHNICAL LTD.
- 13. GEOTECHNICAL ENGINEER TO REVIEW AND APPROVE ALL EARTHWORKS. THE CONTRACTOR SHALL NOT BEGIN BACKFILL OPERATIONS UNTIL THE EXCAVATION WORKS AND SUB-GRADE COMPACTION HAVE BEEN APPROVED BY THE GEOTECHNICAL ENGINEER.
- 14. THE CONTRACTOR SHALL MAINTAIN ALL MUNICIPAL ROADS PROVIDING ACCESS TO THE CONSTRUCTION SITE AND ARRANGE FOR ADEQUATE STREET CLEANING
- 15. THE CONTRACTOR SHALL MAINTAIN SERVICES AND ACCESS TO EXISTING BUSINESSES AND RESIDENCES AT ALL TIMES. ANY DISRUPTIONS THAT ARE UNAVOIDABLE WILL REQUIRE A MINIMUM OF 48 HOUR NOTICE. SINGLE LANE TRAFFIC MUST BE MAINTAINED AT ALL TIMES. THE CONTRACTOR SHALL AT ALL TIMES IMPLEMENT AND MAINTAIN ADEQUATE TRAFFIC CONTROL TO ENSURE THE CONVENIENCE AND SAFETY OF THE TRAVELING PUBLIC, THE SAFETY OF THE WORKERS ON THE PROJECT AND THE PROTECTION OF THE WORK TO THE SATISFACTION OF WEDLER ENGINEERING AND THE OWNER.
- 16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL APPROPRIATE MEASURES TO ENSURE THE SAFETY OF PEDESTRIANS AND CYCLISTS, AND THE SECURITY OF THE WORK AREA DURING CONSTRUCTION. ALL EXCAVATION LEFT OPEN DURING NON-CONSTRUCTION AND UNSUPERVISED PERIODS SHALL BE ADEQUATELY FENCED
- 17. THE CONTRACTOR SHALL BE REGISTERED WITH THE WORKERS COMPENSATION BOARD AND PROVIDE CLEARANCE LETTER TO THE CITY OF COURTENAY.
- 18. THE CONTRACTOR SHALL RECORD ON A CURRENT SET OF PLANS IN A NEAT MANNER, ALL CHANGES ADDITIONS AND DELETIONS TO REFLECT THE "AS CONSTRUCTED" INSTALLATION. THE SET OF PLANS SHALL BE RETURNED TO WEDLER ENGINEERING AT THE COMPLETION OF THE WORKS AND PRIOR TO THE ISSUANCE OF SUBSTANTIAL PERFORMANCE.
- 19. ALL SERVICE TRENCHES AND BACKFILLING SHALL BE CONSTRUCTED TO MMCD DRAWING G4. GRANULAR PIPE BEDDING MATERIAL SHALL BE PER MMCD STANDARDS SECTION 31 05 17 2.7.
- 20. CONTRACTOR TO CALL 'BC ONE ALL' TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION.
- 21. THE CONTRACTOR ASSUMES 'PRIME CONTRACTOR' STATUS FOR THE DURATION OF CONSTRUCTION.
- 22. ALL WORKS ARE TO BE INSTALLED UNDER THE DIRECTION OF AN ENVIRONMENTAL MONITOR AND ARE TO MITIGATE MIGRATION OF SILTS/SANDS BY AIR, WATER,
- 23. A CITY OF COURTENAY TREE CUTTING PERMIT IS REQUIRED PRIOR TO THE REMOVAL OF ANY TREES.
- 24. TRAFFIC PLAN REQUIRED FOR MOBILIZATION AND USE OF EQUIPMENT, AND FOR PEDESTRIAN CONTROL/ACCESS DURING WALKWAY CLOSURES.
- 25. ANY DAMAGES TO THE CITY'S INFRASTRUCTURE MUST BE REPORTED BY THE CONTRACTOR TO THE PUBLIC WORKS YARD AND TO THE ENGINEER OF RECORD IMMEDIATELY.
- 26. PRIOR TO CONSTRUCTION WITHIN THE CITY ROAD RIGHT OF WAY, CONTRACTOR TO OBTAIN A CITY CONSTRUCTION PERMIT.
- 27. THE CONTRACTOR'S 'AS-CONSTRUCTED' DRAWING MARKUPS TO SHOW STRUCTURAL FILL WHERE PLACED IN DEPTHS 0.6m OR GREATER AS REQUIRED WITHIN BUILDING ENVELOPE AND ROAD RIGHT-OF-WAY.

### STORM

- 1. ALL STORM SEWER PIPE AND FITTINGS SHALL CONFORM TO CURRENT MMCD SPECIFICATIONS AND THE CURRENT CITY OF COURTENAY SUBDIVISION AND DEVELOPMENT SERVICING BYLAW 2919.
- 2. ALL STORM SEWER PIPE SHALL BE PVC AND SHALL CONFORM TO ASTM D3034 MIN. CLASS DR35 STANDARDS. PIPE LESS THAN 200mm DIAMETER IS TO BE DR28. ALL PIPE SHALL BE JOINTED WITH RUBBER GASKETS OR GASKETED FITTINGS OR
- 3. ALL STORM SEWER PIPE SHALL HAVE A MINIMUM COVER OF 1.0m FROM PIPE OBVERT TO FINAL GRADE. ANY STORM SEWER PIPE WITHOUT MINIMUM COVER SHALL BE INSULATED TO MANUFACTURER'S SPECIFICATIONS.
- 4. HORIZONTAL DEFLECTION OF STORM SEWER PIPE NOT TO EXCEED ONE-HALF OF MANUFACTURER'S RECOMMENDATION.
- 5. ALL SERVICE TRENCHES AND BACKFILLING TO BE CONSTRUCTED PER MMCD DRAWING # G4 SPECIFICATIONS.
- 6. ALL MANHOLES TO BE PRECAST CONCRETE PER MMCD DRAWING # S1 SPECIFICATIONS.
- 7. CONNECTION TO THE EXISTING MAIN SHALL BE COMPLETED UNDER THE SUPERVISION OF THE CITY.
- 8. CONTRACTOR TO PERFORM VIDEO INSPECTION ON ALL STORM SEWER PIPES & MANHOLES INSTALLED PRIOR TO PAVING OR COMMISSION OF THE SYSTEM.

### SANITARY

- 1. ALL SANITARY SEWER PIPE AND FITTINGS SHALL CONFORM TO CURRENT MMCD SPECIFICATIONS AND THE CURRENT CITY OF COURTENAY SUBDIVISION AND DEVELOPMENT SERVICING BYLAW 2919.
- 2. ALL SANITARY DRAINAGE PIPE 100mm AND 150mm DIAMETER MUST BE SDR 28.
- 3. ALL SANITARY SEWER PIPE SHALL BE PVC AND SHALL CONFORM TO ASTM D3034 MIN. CLASS DR35 STANDARDS. PIPE LESS THAN 200mm DIAMETER IS TO BE DR28. ALL PIPE SHALL BE JOINTED WITH RUBBER GASKETS OR GASKETED FITTINGS OR COURT
- 4. ALL SANITARY SEWER PIPE SHALL HAVE A MINIMUM COVER OF 1.0m FROM PIPE OBVERT TO FINAL GRADE. ANY SANITARY SEWER PIPE WITHOUT MINIMUM COVER SHALL BE INSULATED TO MANUFACTURER'S SPECIFICATIONS.
- 5. HORIZONTAL DEFLECTION OF SANITARY SEWER PIPE NOT TO EXCEED ONE-HALF OF MANUFACTURER'S RECOMMENDATION.
- 6. ALL SERVICE TRENCHES AND BACKFILLING TO BE CONSTRUCTED PER MMCD DRAWING # G4 SPECIFICATIONS.
- 7. CONNECTION TO THE EXISTING MAIN SHALL BE COMPLETED UNDER THE SUPERVISION OF THE CITY.
- 8. CONTRACTOR TO PERFORM VIDEO INSPECTION ON ALL SANITARY SEWER PIPES & MANHOLES INSTALLED PRIOR TO PAVING OR COMMISSION OF THE SYSTEM.


### WATER

- 1. ALL WATER PIPE AND FITTINGS SHALL CONFORM TO CURRENT MMCD SPECIFICATIONS AND THE CURRENT CITY OF COURTENAY SUBDIVISION AND DEVELOPMENT SERVICING BYLAW 2919.
- 2. ALL WATERMAIN PIPE SHALL HAVE A MINIMUM COVER OF 1.0m BETWEEN PIPE OBVERT AND FINAL GRADE. WHERE MINIMUM COVER CANNOT BE MET WATER MAIN TO BE CONCRETE ENCASED PER MMCD DWG G7. CROSSINGS OF SEWERS BELOW MINIMUM COVER SHALL BE PER MMCD DWG G6.
- 3. ALL SERVICE TRENCHES AND BACKFILLING TO BE CONSTRUCTED PER MMCD DRAWING # G4 SPECIFICATIONS.
- 4. ALL WATERMAIN PIPE SHALL BE DR-18 PVC TO AWWA C900, CSA 137.3, CLASS 1035 UNLESS NOTED OTHERWISE.
- 5. ALL WATERMAIN FITTINGS SHALL BE CAST IRON TO AWWA C110 STANDARDS OR INJECTION MOULDED PVC TO AWWA C907.
- 6. ALL WATERMAIN FITTINGS ONSITE TO HAVE MECHANICAL JOINT RESTRAINTS OR CONCRETE THRUST BLOCKS PER CITY OF COURTENAY SUPPLEMENTARY SPECIFICATIONS. ALL WATERMAIN FITTINGS OFFSITE TO BE RESTRAINED BY MECHANICAL RESTRAINTS ONLY WITHOUT THE USE OF CONCRETE THRUST BLOCKS.
- 7. ALL INSTALLED WATER PIPE SHALL BE PRESSURE TESTED PER MMCD SECTION 33 11 01.
- 8. ALL INSTALLED WATER PIPE SHALL BE DISINFECTED, FLUSHED & BACTERIOLOGICALLY TESTED PER MMCD SECTION 33 11 01.
- 9. MINIMUM VERTICAL SEPARATION BETWEEN A WATERMAIN AND ANY STORM OR SANITARY PIPE SHALL BE 0.45m. WHERE WATERMAIN CROSSINGS OF SANITARY/STORM OCCUR, WRAP ALL WATERMAIN, STORM AND SANITARY JOINTS INCLUDING TEES, BENDS, REDUCERS, VALVES, CROSSES ETC WITHIN 3.0m OF CROSSING. JOINT WRAP TO AWWA/ANSI C209 (CANUS 'JointWrap' COLD APPLIED JOINT SLEEVE OR APPROVED ALTERNATE).
- 10. CONNECTION TO THE EXISTING MAIN SHALL BE COMPLETED UNDER THE SUPERVISION OF THE CITY. CONTRACTOR TO PREPARE AND SUBMIT A WATER TIE-IN SEQUENCE/METHODOLOGY PLAN TO THE PROJECT ENGINEER FOR SUBMISSION TO THE CITY FOR APPROVAL, PRIOR TO SCHEDULING TIE-IN WORKS.

			<b>EDLE</b>	-				DRAII	NAGE S	SYSTEN	A DESIG	GN - CA	LCUL	ATION S	SHEET							
Client:		Bartle a	nd Gibson	Co. Ltd.				Date:		8/22/	2022											
Project:			adrona Pla	10 10 10 10 10 10 10 10 10 10 10 10 10 1				Date Printe	d:	8/31/				DESIGN	RETUR	N PERIO	D: 10 ve	ear / 100 y	ear			
Project	<u>#</u> :	V22-055						By:		T.	ID			Commercia								
Jest																	Puntledge	VCHP ID:	1021990'	DF Data used	d for calculation	ns
														-15% Incre	ease from I	Historical Int	ensities					
F	ipe Run In	fo		9	Drainage Are	a Paramete	rs		IDF	Info.	Flow Cal	culations					Pipe De	esign				
Ma	nhole	Length	Catchment	Catch. Area	Runoff Coeff.		Cummalitive	Cummalitive		sities	1:10 year	1:100 year		Pipe Rough.	Slope	Pipe at		Time			% Capacity	% Capacity
-		L	Identifier	A	R	R*A	(R*A)	Te	I10	I100	Q10	Q100	D	n	S	Qcap	Vcap	t	Qcap-Q10		10-Year	100-Year
From	То	(m)		(m²)		(m²)	(m²)	(minutes)	(mm/hr)	(mm/hr)	(m³/s)	(m³/s)	(mm)		(%)	(m³/s)	(m/s)	(minutes)	(m³/s)	(m³/s)	(%)	(%)
LB205	СВМ Н4	39	A9	227	0.20	45	45	5.00	82.40	149.00	0.001	0.002	150	0.013	1.8	0.020	1.16	0.56	0.019	0.019	5	9
	СВМНЗ	44	A10, A11	335	0.42	141	186	5.56	78.31	140.95	0.004	0.007	150	0.013	1.00	0.015	0.86	0.85	0.011	0.008	27	48
LB204	LB203	30	A8	236	0.20	47	47	5.00	82.40	149.00	0.001	0.002	150	0.013	1.50	0.019	1.06	0.47	0.018	0.017	6	10
LB203	FCMH2	32	A7	391	0.20	78	125	5.47	78.92	142.13	0.003	0.005	150	0.013	1.50	0.019	1.06	0.51	0.016	0.014	15	27
LB201	LB200	21	A1	99	0.20	20	20	5.00	82.40	149.00	0.000	0.001	150	0.013	1.00	0.015	0.86	0.41	0.015	0.014	3	5
LB200	FCMH2	4	A2	73	0.20	15	34	5.41	79.38	143.06	0.001	0.001	150	0.013	3.00	0.026	1.49	0.04	0.026	0.025	3	5
ROOF1	OS 1	18	A12	1,582	0.90	1,424	1,424	5.00	82.40	149.00	0.033	0.059	200	0.013	2.00	0.046	1.48	0.20	0.014	-0.013	70	127
KUUFI	05 1	18	A1Z	1,584	0.90	1,424	1,424	3.00	82.40	149.00	0.033	0.039	200	0.013	2.00	0.046	1.48	0.20	0.014	-0.013	/0	127
LB202	СВМНЗ	21	A5	253	0.20	51	51	5.00	82.40	149.00	0.001	0.002	150	0.013	1.30	0.017	0.98	0.36	0.016	0.015	7	12
	FCMH2	38	A3,A4,A6	2,600	0.90	2,340	2,577	5.36	79.74	143.75	0.057	0.103	300	0.013	1.00	0.097	1.37	0.46	0.040	-0.006	59	106
FCMH2	OS 1	6	-	_	-	-	4,001	5.82	76.64	137.67	0.085	0.153	300	0.013	10.31	0.310	4.39	0.02	0.225	0.158	27	49
OS 1	DMH50	9	_	-	_	-	4,160	5.84	76.50	137.39	0.088	0.159	300	0.013	5.00	0.216	3.06	0.05	0.128	0.057	41	73

								-		_
LEGAL	:	Α	ISSUED FOR DEVELOPMENT PERMIT	2022-02-28	TJD					
	LOT B	В	RE-ISSUED FOR DEVELOPMENT PERMIT	2022-03-30	TJD					
	VIP85381	C	RE-ISSUED FOR DEVELOPMENT PERMIT	2022-09-01	TJD					
	PID 027-585-166									
	CIVIC: #4625									
BM/ TBM:	GNSS OBSERVATIONS									
IDM:	ELEV'S REF'D TO:									
	V. DATUM CGVD28	REV	DESCRIPTION	YYYY-MM-DD	BY	REV	DESCRIPTION	YYYY-MM-DD	BY	1_







www.wedler.com

	THE WEDLE
	■ Abbotsfo 1.604.746
LER	■ Chilliwad 1.604.792
ERING	■ Courtena 1.250.334

THE WEDLER GROUP	BARTLE AND GIBSON CO. LTD.	DRAWING NO. OF 6
■ Abbotsford 1.604.746.0300	COMMERCIAL DEVELOPMENT - 4625 MADRONA PLACE	V22-0552/A-05
■ Chilliwack	COURTENAY, BC	
1.604.792.0651 ■ Courtenay 1.250.334.3263	CENEDAL NOTES STORM CALCULATIONS	LOCAL GOVERNMENT FILE
■ Surrey 1.604.588.1919	GENERAL NOTES, STORM CALCULATIONS AND MISCELLANEOUS DETAILS	PHASE REVISION



LEGAL	:	Α	ISSUED FOR DEVELOPMENT PERMIT	2022-02-28	TJD					
	LOT B	В	RE-ISSUED FOR DEVELOPMENT PERMIT	2022-03-30	TJD					
	VIP85381	С	RE-ISSUED FOR DEVELOPMENT PERMIT	2022-09-01	TJD					
	PID 027-585-166									
	CIVIC: #4625									
BM/ TBM:	GNSS OBSERVATIONS									
IBM:	ELEV'S REF'D TO:									
	V. DATUM CGVD28	REV	DESCRIPTION	YYYY-MM-DD	BY	REV	DESCRIPTION	YYYY-MM-DD	BY	
0022	WEDLER ENCINEERING LIR ALL DIC	ישדכ סם	SERVED THIS DOCUMENT IS PROTECTED BY CORVEIGHT LAW AND MAY NOT	DE DEDDODINE	D IN AN	V MANIA	IED OD EOD ANY DIIDDOSE EVCEDT DY WDITTEN DEDNISSION OF CODYDICUT L	JOI DEB		_



	PROJ. MGR.	RAV
/	DESIGN/DRAWN	TJE
	PEER REVIEWED	RAV
	HORIZ. SCALE	N.T.
6	VERT. SCALE	_



	1.604.746.0300
LEK	■ Chilliwack 1.604.792.0651
ERING	■ Courtenay 1.250.334.3263

■ Surre	ey
1.60	4.588.1919

ARTLE AND GIBSON CO. LTD.	DRAWING NO.	OF 6			
MMERCIAL DEVELOPMENT - 4625 MADRONA PLACE	V22-0552/A-06				
DURTENAY, BC	-				
	LOCAL GOVERNMENT FILE				
MERGENCY 100-YEAR OVERFLOW ROUTE					
WILINGLING I TOO TEAN OVENI LOW NOOTE	PHASE	REVISION			
		С			